Certificate of Completion for Engineering Services

Applicant	Company Name	Korea Rural Community Corporation (KRC)	Representative of the company	In Joong KIM
	Place of Business	Green-ro 20, Naju-si, Jeollanam-do, Korea	Telephone No.	+82-61-338-5114
	Business Registration No.	135-82-08470	Place to Submit	Client
	Use of Certificate	Prequalification for engineering services of the company		
	Contract Amount	■ Total Contract Amount: USD 15, 585,355.17 (KRW 17,386,087,100.00) - Construction Supervision Stage: USD 5,990,833.17 (KRW 6,683,014,028.12, $1=1,115.54won) (KRC:SAMAN:DASAN=40:30:30)		

Description of Implemented Services	Project Name	Consulting Service for Detailed Design and Construction Supervision for Jalaur River Multi-Purpose Project Stage II	Classification	Detailed Design (○) Construction Supervision (○)

Summary of Services

1. Objective of Project

The Government of the Philippines, through the National Irrigation Administration (NIA) intends to carry out the Jalaur River Multi-Purpose Project Stage II in order to relieve poverty and generate employment opportunities with increased agricultural production.

The project objectives have been defined as follows.

- To provide year-round irrigation for increased agricultural production to 22,340ha of 5 existing irrigation systems and 9,500ha of currently rain fed areas
- To build a penstock that is ready for a 6.6 MW Hydroelectric Power Plant to supplement the power supply in the province
- To augment supply of bulk water for domestic and industrial consumption in the nearby municipalities including Iloilo City
- To realize other intangible benefits including flood mitigation and promotion of eco-tourism in selected dam/reservoir areas

2. Project Location: Calinog, Iloilo Province, Philippines

3. Details of Services

▪ 3 Dams
- Jalaur High Dam (H=109m, Gravity Dam, RCC Method) / Diversion TL (L=290.0m, NATM)
- Jalaur Afterbay Dam (H=40m, Gravity Dam, RCC Method) / Diversion TL (L=130.0m, NATM)
- Alibunan Catch Dam (H=10m, Gravity Dam)
- Appurtenant Structures

▪ High Line Canal
- Total Length, L=80.74km
- Concrete Lined
- Appurtenant Structures (siphon, conduit, wasteway, check gate, head gate, water supply tapping point, etc.)

▪ New Irrigation Areas
- Service Area, A=9,500ha
- Main Canal (L=60.4km, concrete lined, trapezoidal, open canal)
- Lateral Canal (Zone 5, L=18.7km, concrete lined, trapezoidal, open canal)
- Connecting Canal (Zone 1, L=1.1km, concrete lined, trapezoidal, open canal)
- Appurtenant Structures (siphon, conduit, drainage culvert, wasteway, service road, check gate, head gate, etc.)

▪ Existing Irrigation Areas
- Service Area, A=22,340ha
- Main Canal (L=65.6km, concrete lined, trapezoidal, open canal)
- Lateral Canal (L=8.6km, concrete lined, trapezoidal, open canal)
- Appurtenant Structures (siphon, wasteway, road crossing, check gate, head gate, etc.)

▪ Access Road (L=6.15km, B=6.0-8.1m, 1-2 lanes), Concrete pavement

▪ Construction Cost : USD 113,505,882.14 (KRW 126,620,351,763)

4. Detailed Design & Construction Supervision Period : November 27, 2013 ~ March 25, 2025

5. List of the Participated Engineers in Detailed Design and Construction Supervision Period

No.	Name	Date of Birth	Position	Period of Participation
1	Sung Soo AN	Jun. 20, 1966	Irrigation Engineer/O&M Specialist	Sep. 01, 2023 ~ Mar. 31, 2025
2	Hee Sung SHIN	Mar. 25, 1972	Geodetic/Construction Engineer	Sep, 20, 2018~ Mar. 10, 2022 Feb. 05, 2024~ Feb. 09, 2025
3	Byoung Woo LEE	May, 10, 1973	Contracts/Monitoring/Evaluation Engineer	Mar. 25, 2024~ Mar. 25, 2025

We hereby certify that the above contents are fact and true. December, 2025

Name of Issuer (Client): **National Irrigation Administration**

Address: Tacas, Jaro, Iloilo City, Philippines

Representative: **Engr. Jonel B. Borres**
Regional Manager / Concurrent Project Manager
National Irrigation Administration/JRMP II
Region 6, Iloilo City

Signature:

Date: 16 JAN 2026